Perimeter Security Fence- East Lake Community Park: 24809 Wallick Rd. Sorrento, FL 32776

1.01 SCOPE OF WORK: Provide all labor, materials, equipment, fuel and other incidental costs and supervision necessary for the removal of the existing temporary fencing and the installation of approximately 980 FT of 8 ' high black vinyl coated 6 gauge schedule 40 chain link fencing. All work and equipment shall be in strict compliance with the latest codes, standards and practices.

Misc. Items to be noted:

- The Contractors installation when completed, shall match the existing 8' Black vinyl coated chain link fence.
- All fencing is to be installed as shown on attached plan.
- All existing fence & posts to be removed and stored next to the maintenance container on site

Fence details for 8 FT High Fencing:

8' High Black Vinyl Coated 6 gauge-schedule 40 chain link fence is required . Steel Chart for schedule of sizes of members is as follows:

Height of fence- 8 FT

Diameter of line posts- 2 1/2 "

Post spacing Max- 6FT

Corner & end post-3 " diameter

Top, Mid & Line Rail –1 5/8" diameter

Depth of post into footing (line post & end / gate/corner post) – 1'-8"

Diagonal Braces – ½ "diameter

Mesh to be placed on the outside of the fencing.

Tie wire, #6 W & M gauge aluminum ties @ 15 o.c. for rails. Ties to be 12" apart on posts. End of ties should be wound in a telegraph, trust 2 ½ turns. Horizontal braces at corner & End posts 1 5/8 "

1.02 SUBMITTALS:

- A. Submit product data/specification and shop drawings to Park and Trails Division for review and approval of all items of work.
- B. All submittals to be approved by Parks and Trails Division prior to contractor delivering materials to site.
- 1.03 FIELD CONDITIONS: Verify and coordinate all work to field locations and dimensions.

1.04 PRODUCT HANDLING:

- A. Deliver products to site in manufacturer's containers or packaging.
- B. Store in secure and weather protected area.
- C. Return all damaged products to manufacturer.

PART II - PRODUCTS

2.01 MATERIALS: Provide products as called for on the drawing and specified herein. See furnishing schedule and descriptions on drawings for specific products and Manufacturer's specs.

. . .

PART III - EXECUTION

3.01 WORKMANSHIP:

- A. All furnishings described herein shall be installed by qualified tradesman. All installation work and materials to be per manufacturer's specifications, or as directed by the Owner's Representative.
- B. All work and materials are subject to the approval of the County.
- C. All products shall be inspected by the County for damage and chipped or marred finish. Contractor shall replace any damaged or rejected products at no conditional cost to the owner. The owner's representative may at his option authorize acceptance of chipped or scratched painted surfaces repaired by contractor at his own risk.

3.1 INSTALLATION

- A. Install furnishing in locations as indicated on the plans and details. Assure that all furnishings are installed plumb and level and in accordance with the plans and details.
- B. Install as per manufacturer's specifications


3.2 ACCEPTANCE


- A. The County will review each installation to determine compliance with plans and specifications prior to final acceptance of the work.
- B. Any work not installed in accordance with the plans and specifications and rejected by the County shall be removed and replaced at the Contractor's expense.


3.4 CLEANING

A. Perform cleaning during installation of the work and upon completion of the work. Remove from site all excess materials, soil, debris, and equipment.











BOULEVARD SCALE: HALF SCALE

A=13/4" FOR 2" - 41/2" O.D. POST B=15/8" FOR 2" O.D. OR SMALLER POST C=21/2" NOM. O.D. OR LARGER - 2 BOLTS REQUIRED







NOTE: MINIMUM WIDTH OF END FITTING TO BE 21/4"

PLAN







SMALL POST CAP

