

Phase 2- Parking Lot Repairs

Astatula Boat Ramp- 12703 Florida Ave. Astatula, FL 34705

- 1.01 SCOPE OF WORK: Provide all labor, materials, equipment, fuel and other incidental costs and supervision necessary for site preparation, cutting, filling and compaction with six (6)" of lime rock sub base and complete installation of three (3) new parking spaces of 1 ½" Type S III Asphaltic pavement. All work and equipment shall be in strict compliance with the latest codes, standards and practices.

Misc. Items to be noted:

- Field verification by Contractor is recommended
- 4" White paint stripe required per FDOT Specs
- 1 ½" Type S-III Asphaltic pavement
- Concrete wheel stops are included in this bid
- Site preparation will be required
- Seamless joint between the existing asphalt and the repair

PART III – EXECUTION

3.01 WORKMANSHIP:

- A. All furnishings described herein shall be installed by qualified tradesman. All installation work and materials to be per manufacturer's specifications, or as directed by the Owner's Representative.
- B. All work and materials are subject to the approval of the County.
- C. All products shall be inspected by the County for damage and chipped or marred finish. Contractor shall replace any damaged or rejected products at no additional cost to the owner. The owner's representative may at his option authorize acceptance of chipped or scratched painted surfaces repaired by contractor at his own risk.

3.02 ACCEPTANCE

- A. The County will review each installation to determine compliance prior to final acceptance of the work.

3.03 CLEANING

- A. Perform cleaning during installation of the work and upon completion of the work. Remove from site all excess materials, soil, debris, and equipment.

Astatula Boat Ramp- 12703 Florida Avenue,
Astatula FL 34705

