

Addendum #1

#5970 Getford Road Regional Stormwater Pond
Project No. 2009-06
Bid No. 09-0825

This project is located northeast of Eustis along #5970 Getford Road. The project will consist of constructing an 8 acre stormwater pond and installing a storm sewer system. Other work associated with this project shall include concrete box culvert construction, asphalt roadway reconstruction, curb installation, thermoplastic striping, sodding, and other miscellaneous incidental construction.

Name	Representing	Phone Number	Email Address
Kathy Barnes	D.A.B. Constructors	352-447-5488	kathrynb@dabcon.com
Michael Barnes	Mid State Paving	863-965-2861	mbspmarketing@tampabay.rr.com
Ken Bare	Ciraco Underground	352-347-2035	kbare@ciracounderground.com
Fred Briggs	James Construction	225-241-3285	jbriggs@jcglc.com
Mick Byroads	Jr. Davis Construction	407-870-0066	buckj@jr-davis.com
Jimmy Conrad	Boykin Construction, Inc.	352-394-5993	bob@boykinconstruction.com
Lito Detorres	PDS, Inc.	352-589-7000	Lito713@comcast.net
Paul Doran	Lake County Public Works	352-483-9084	pdoran@lakecountyfl.gov
Ben Driver	Lake County Public Works	352-483-9090	bdriver@lakecountyfl.gov
Mike Gayle	James Construction	225-241-3016	mgayle@jcglc.com
Ron Green	Florida Silt Fencing, Inc.	877-435-7458	rgreen@flsilt.com
Mary Hamilton	Lake County Public Works	352-483-9080	mhamilton@lakecountyfl.gov
David Hamstra	Professional Engineering Consultants	407-422-8062	dwh@peconline.com
Laurie Henderson	J. Malever Construction, Inc.	352-429-9507	tomsmithjmc@embarqmail.com
Ted Hunter	CE James Inc.	407-359-5533	jimcejames@yahoo.com
Jeff Johnson	Lake County Public Works	352-483-9024	jjohnson@lakecountyfl.gov
Michael Krones	Hubbard Construction	407-645-5500	Michael.krones@hubbard.com

Name	Representing	Phone Number	Email Address
Joe Liakos	Amick Construction, Inc.	407-293-6562	Joe@amickinc.com
Heath McArdle	Lake County Public Works	352-483-9027	hmcardle@lakecountyfl.gov
Sherry McDermott	Lake County Public Works	352-483-9020	smcdermott@lakecountyfl.gov
Tom Miller	Art Walker Construction, Inc.	352-629-1466	artwalkerconst@hughes.net
Pete Morgan	Ranger Construction	407-656-9255	pmorgan@rangerconstruction.com
Ashton Rainey	Rainey Construction	352-748-0955	arainey@raineyconstruction.com
Rohan Ross	Hubbard Construction	407-645-5500	Rohan.ross@hubbard.com
Fred Spielmann	Wal-Rose Inc.	407-328-9999	fred@wal-rose.com

Items Discussed:

- Cost of all required laboratory testing shall be borne by the County with the exception of the cost of failing tests and subsequent re-tests which shall be borne by the Contractor. Testing shall be in accordance with the Standard Specifications.
- The Contractor is to map and match all existing striping. All striping is to be 6" thermoplastic.
- Add a line item on your bid tabulation sheet for driveway construction.
- Add a line item on your bid tabulation sheet for concrete removal.
- The Geotechnical report is posted on the Lake County Procurement Services Department's website:

http://www.lakecountyfl.gov/departments/procurement_services/bid_details.aspx?bid_number=09-0825

- The Auto Cad File for this project is posted on Lake County's FTP site:
ftp://ftp.co.lake.fl.us/Public_Works/Funding_Production/
- On page 17 of 17 of the construction plans on detail #7 in the pavement replacement detail, change the ¾" of type S-III Asphalt to 1" of type S-III Asphalt to match the milling details shown in the construction plans.

- This is a joint project between the City of Eustis and Lake County. We are utilizing property owned by the City of Eustis to build the 8 acre pond. The area around the pond can be used for a staging area. The surrounding area along the project is mostly residential with some agriculture areas located on the North side of the street.
- The City of Eustis may have their inspectors visit the site during construction.
- David Hamstra with PEC mentioned that several vendors have requested using alternates for the box culverts. The project shall be constructed using the box culverts as designed. The culverts are to be constructed as per the construction plans.
- David Hamstra with PEC mentioned there is an existing 16" reclaimed water line located on the North side of Getford Road, which is why the storm pipe is located underneath the roadway. David also mentioned that there are numerous other utilities located in this area. He also mentioned that the project area has a past history of severe flooding.

Question and Answers:

Q. Are there any permit fees required by the County or the City?

A. The contractor will be responsible for paying for their NPDES permitting.

Q. What is the budget?

A. The Engineer's estimate is \$2,918,322.00.

Q. Is an Excel Spreadsheet of the tabulation sheet available?

A. Yes, the tabulation sheet in Excel format with the revised line items shall be posted on the Lake County Procurement Services Department's website:

http://www.lakecountyfl.gov/departments/procurement_services/bid_details.aspx?bid_number=09-0825.

Q. Who takes ownership of the dirt from the project?

A. All excavated material shall become the property of the awarded contractor.

Q. Is the project site clear of trees?

A. There are some existing trees; however, we have designed the pond around a majority of them. The actual foot print of the pond is mostly clear of trees.

Q. The soil borings show water elevations, are they the typical water elevations?

A. The Geotechnical report should show the encountered and predicted seasonal high water elevations along the project corridor.

Q. Does the contractor have to maintain traffic on Getford Road during construction?

A. Yes, road closure in segments will be allowed as there are numerous detour routes along the project. The awarded contractor must supply to Lake County a maintenance of traffic plan for review and approval.


Q. What is the estimated time frame to begin the project?

A. The project should begin in 60-90 days.

Q. Do you have an estimated time frame for project completion?

A. The contractor shall supply the numbers of days for project completion.

Approved by:



Jeff Johnson, Construction Inspection Manager

7/30/09

Date

:smcd