



OFFICE OF PROCUREMENT SERVICES
315 WEST MAIN STREET, SUITE 416
POBOX 7800
TAVARES, FL 32778-7800

PHONE: (352) 343-9839
FAX: (352) 343-9473

www.lakegovernment.com

Addendum No .01
Date: June 9, 2010
ITB: 10-0035
Full Depth Reclamation (FDR) at Royal Trails

This addendum is being issued to make the following changes to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents.

Respondents shall acknowledge receipt of this addendum by completeing this form and returning it with the response. Failure to acknowledge this addendum may preclude consideration of the bid proposal award.

On page 4, Section 2.5: Contract Performance Period: the wording changed from “on the first calendar day of the month” to “upon issuance of Notice to Proceed.”

On page 7–sub-letter C.: the wording changed from “four (4)” to “five (5)”.

On page 12, Section 4.1: Specifications: the wording changed from “Asphalt” to “Cement”

On page 13 ITB Title: the wording changed from “Asphalt” to “Cement”

On page A14 under Incidental Repairs: the wording changed from "...within twenty four (24) hours..." to "...within twenty four (24) to seventy-two (72) hours..."

On page A17 Section 1 title: the wording changed from "Asphalt" to "Cement"

On page A17 1.4. Materials: wording change from "... modified Marshall Tests" to "... molded pills"

On page A19–1.7: the wording changed from "...75mm (3 inches)." to "... 50mm (2.5 inches)."

On page A19–1.7: the wording changed from "...shall not exceed (8.0")..." to "...shall not exceed (10")..."

On page A20–1.10 Testing: the wording changed from "...ninety-eight percent..." to "...nintey-five percent..."

On page A21–2.5 Prime and Tack Coats: the following additional wording was added: "If prime coat is used no need to tack coat, if done the same day."

On page A22, Testing and Sampling Schedule Chart, under the Tests heading "Marshall Stabiliy" was deleted.

On page A22, Testing and Sampling Schedule Chart, under the Project Requirements head, the wording changed from "98% Control Strip" to "(92% Maximum Specific gravity G mm"

On page A22, Testing and Sampling Schedule Chart, under the Project Requirements head, the wording changed from "98% proctor" to "95% molded proctor"

On page A22, Testing and Sampling Schedule Chart, under the Testing Frequency head, the wording changed from "all lanes of roadway every 500 feet" to "per FDOT specifications 334-5.1.1.2. Ominting 1,000 ft minimum for cores"

On page A23–2.10, the word Contractor was misspelled. It read "CONTRACCTOR" it now reads "CONTRACTOR"

On page A26–2.12 Shoulder Rehabilitation, the wording changed from “...appropriate test method.” to “...modified proctor test.”

On page A26–2.12 Shoulder Rehabilitation, the wording changed from “...98%...” to “...95%”

Firm Name: _____ Date: _____

Signature: _____ Title: _____

Typed/Printed Name: _____