Addendum #3
CR-44 Intersection with CR-44 Leg A,
Project No. 2011-07
Bid No. 12-0008

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-4 of the bid proposal**. Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

Q. Bid Form-Tabulation of estimated Quantities has three items for limerock base. Typical Section sheets 6 & 7 both have a requirement for 8" limerock, but the quantity sheet has a 6", 8" and 10" limerock item. Should the 6" and 10" limerock items be removed from the bid form?

A.
- 6" Limerock to be used to construct any asphalt driveways as shown in the detail on sheet 5.
- 8" Limerock to be used to construct Shady Acres road as stated in the project description.
- 10" Limerock to be placed in the widening section of CR 44 as stated in the project description.

Approved by:

Jeff Johnson, Construction Inspection Manager

10/4/11
Date

:smcd