

Pre-Bid – Addendum #1
 Sunset Avenue Improvements
 Project No. 2011-09
 Bid No. 12-0017

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-4 of the bid proposal.** Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

A non-mandatory pre-bid meeting for the referenced project was held at 9:00 a.m. on December 15, 2011 in the Department of Public Works' conference room. The following were in attendance:

Name	Company	Phone Number	Email Address
Kathryn Barnes	D.A.B. Constructors, Inc	(352) 447-5488	kathrynb@dabcon.com
David Berger	Lake County Public Works	(352) 394-2559	dberger@lakecountyfl.gov
J. J. Bonnisuto	Flamingo Concrete	(352) 552-7874	jjflamingo@gmail.com
Denis Dietz	Lake County Public Works	(352) 742-1766	ddietz@lakecountyfl.gov
Seth Lynch	Lake County Public Works	(352) 483-9052	slynch@lakecountyfl.gov
Zack Behring	UCF Engineering Intern		
Chris O'Neil	Boykin Construction, Inc	(352) 394-5993	bob@boykinconstruction.com
Curtis Upshaw	City of Mascotte	(352) 429-4429	Curtis.upshaw@cityofmascotte.com
Alan Kirkland	Lake County Public Works	(352) 483-9043	akirkland@lakecountyfl.gov
Sherry McDermott	Lake County Public Works	(352)483-9020	smcdermott@lakecountyfl.gov
Ron Rudolph	Lake County Public Works	(352)483-9021	rrudolph@lakecountyfl.gov
Terry Scott	Lake County Public Works	(352)483-9023	jscott@lakecountyfl.gov

This project is located in Mascotte along North and South Sunset Avenue and shall consist of road widening, constructing 2' paved shoulders, and resurfacing. Construction shall consist of milling the existing roadways 1" in depth, 12" type B stabilized subbase (98% compaction), 10" limerock base placed in two (2) 5" lifts (98% compaction each lift, primed and sanded), 2" minimum SP 12.5 asphaltic concrete, 0.5" SP-9.5 asphaltic concrete leveling course, and 1" minimum SP-9.5 asphaltic concrete. Other work associated with this project shall include the following: thermoplastic striping, storm structure installation, swale work, driveway construction, roadway signage, concrete sidewalk, handicap ramps, guardrail, gravity wall, type F curb, sodding and other miscellaneous incidental construction.

- There are eight typical sections contained in the construction plans.
- Sidewalk and handicap ramps must meet all current ADA standard specifications.
- Pay attention to all notes shown in the construction plans.
- The Engineers Estimate is \$1,054,000.00.

- Work performed under this contract shall be based on a lump sum bid. Quantities, if shown in the bid, are estimated for bidding purposes only and shall be verified by the contractor.
- Contractor shall provide two (2) red lined, complete copies of plans as as-built drawings for the project.
- Contractor shall video the project limits prior to beginning construction. The video shall be in DVD format and provided to Lake County **before** construction begins. Detail should be given to all existing fence lines, driveways, hedge lines, etc., to document existing conditions prior to construction.
- Any questions shall be submitted in writing by **December 20, 2011** to Sherry McDermott via email at smcdermott@lakecountyfl.gov and will be responded to through the issuance of an addendum. **Please be sure that all addendums are acknowledged by signing and dating the appropriate line on page W-4 of the bid proposal.** Addendums will be posted on Lake County's Procurement Services website. The website link for this project is provided below:

http://www.lakecountyfl.gov/departments/county_manager/procurement_services/bid_details.aspx?bid_number=12-0017


Questions and Answers:

Q. Is a CAD file available for this project?

A. Yes, the CAD file is located on the FTP site at the following link:

[ftp://ftp.co.lake.fl.us/Public Works/Road%20Operations/Sunset%20Avenue%20Improvements/](ftp://ftp.co.lake.fl.us/Public%20Works/Road%20Operations/Sunset%20Avenue%20Improvements/)

Approved by:



Ron Rudolph, Construction Inspection II

Date 12-16-11

:smcd