

ADDENDUM #1

Villa City Road Bridge and Water Quality Improvements
Project No. 2012-05, Bid No. 12-0031

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-4 of the bid proposal.** Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

A non-mandatory pre-bid meeting for the referenced project was held at 10:00 a.m. on August 2, 2012, in the Department of Public Works' conference room. The following were in attendance:

Name	Company	Phone Number	Email Address
Holly Strout	WBE Environmental dba FL Silt Fencing	(386) 753-0575	estimating@flsilt.com
Alicia Roehn	Traverse Group	(352) 409-6630	aroehn@traversegroup.com
Manuel Rodriguez	APEC	(407) 522-0530	manuel@apec.us
Dale Mudrak	Gregori Construction	(321) 438-1879	dmudrak@gregori-inc.com
Rick Fender	Fender Marine	(407) 481-2750	rick@fendermarine.com
Chris O'Neil	Boykin Construction	(353) 394-5993	boykinconst@aol.com
Pat Magno	Lake County Public Works	(352) 483-9053	pmagno@lakecountyfl.gov
Terry Scott	Lake County Public Works	(352) 483-9023	jscott@lakecountyfl.gov
Mary Hamilton	Lake County Public Works	(352) 483-9080	mhamilton@lakecountyfl.gov
Heath McArdle	Lake County Public Works	(352) 483-9084	hmcardle@lakecountyfl.gov
Deb Marchese	Lake County Public Works	(353) 483-9007	dmarchese@lakecountyfl.gov

This project is located north of Groveland along Villa City Road (CR 565) and shall consist of bridge abutment rehabilitation, and storm drainage improvements. Other work associated with this project include the construction of a soldier pile and concrete lagging system, retention pond construction, storm structure installation, swale work, sod, and other miscellaneous incidental construction. The engineer's estimate is \$388,201.80.

Work performed under this contract shall be based on a lump sum bid. Quantities, if shown in the construction plans, are estimated for bidding purposes only and shall be verified by the contractor.

Pay special attention to all notes shown in the construction plans.

Contractor shall video the project limits prior to beginning construction. The video shall be in DVD format and provided to Lake County before construction begins. Detail should be given to all existing fence lines, driveways, hedge lines, etc., to document existing conditions prior to construction.

Bid to sod all disturbed areas matching all existing grass types. Contractor shall be responsible for watering all sod until there is established growth.


All utilities shown in the construction plans to be relocated shall be the responsibility of the utility provider to relocate. The contractor shall be responsible for utility relocation coordination.

Contractor shall bid to clear the entire right of way within the limits of the Villa City Road Bridge and Water Quality Improvements project. However, due to local resident concerns, no clearing along the right of way of Villa City Road (CR-565) shall be performed without prior approval from the Lake County Construction Inspection Department. Lake County staff will meet onsite with the awarded contractor to mark all trees and shrubs that are to be removed. It is our intent to leave as much existing vegetation in place as possible.

Any correspondence or questions regarding this project should be directed to Deb Marchese, Lake County Public Works, 437 Ardice Avenue, Eustis, FL 32726, (352) 483-9007, dmarchese@lakecountyfl.gov.

Q: What are the coating specifications (if any) for the soldier piles and concrete lagging for the referenced project?

A: There shall be no coating required for the soldier piles and concrete lagging.



Terry Scott, Construction Inspector II