

## ADDENDUM #1

CR 450 (Collins Street) Intersection with SR 19  
Project No. 2013-01  
Bid No. 13-0013  
FPN #429260-58-01

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-4 of the bid proposal.** Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

A non-mandatory pre-bid meeting for the referenced project was held at 9:00 a.m. on January 3, 2013, in the Department of Public Works' conference room. The following were in attendance:

Name	Company	Phone Number	Email Address
Blair Johnson	Ranger Construction	(407) 656-9255	<a href="mailto:estimating@rangerconstruction.com">estimating@rangerconstruction.com</a>
Kathryn Barnes	D.A.B. Constructors	(352) 447-5488	<a href="mailto:kathrynb@dabcon.com">kathrynb@dabcon.com</a>
Kacy Boykin	Boykin Construction	(352) 394-5993	<a href="mailto:boykinconst@aol.com">boykinconst@aol.com</a>
Denis Dietz	Lake County Public Works	(352) 742-1766	<a href="mailto:ddietz@lakecountyfl.gov">ddietz@lakecountyfl.gov</a>
Noble Olasimbo	Lake County Public Works	(352) 483-9092	<a href="mailto:nolasimbo@lakecountyfl.gov">nolasimbo@lakecountyfl.gov</a>
Jeff Johnson	Lake County Public Works	(352) 483-9024	<a href="mailto:jjohnson@lakecountyfl.gov">jjohnson@lakecountyfl.gov</a>
Terry Scott	Lake County Public Works	(352) 483-9023	<a href="mailto:jscott@lakecountyfl.gov">jscott@lakecountyfl.gov</a>
Benny Caldwell	Lake County Public Works	(352) 483-9021	<a href="mailto:bcaldwell@lakecountyfl.gov">bcaldwell@lakecountyfl.gov</a>
Alan Kirkland	Lake County Public Works	(352) 483-9043	<a href="mailto:akirkland@lakecountyfl.gov">akirkland@lakecountyfl.gov</a>
Deb Marchese	Lake County Public Works	(353) 483-9007	<a href="mailto:dmarchese@lakecountyfl.gov">dmarchese@lakecountyfl.gov</a>

This project is located in Umatilla at the intersection of CR 450 (Collins Street) and SR 19 and shall consist of constructing turn lanes and paved shoulders, installing a traffic signal, and constructing a 10' in width pedestrian walkway. Other work associated with this project shall include the following: Type E curb, asphalt milling, thermoplastic striping, storm structure installation, roadway signage, sodding and other miscellaneous incidental construction. This project involves work on a State Highway and the contractor must be an FDOT Prequalified Contractor and have knowledge of FDOT Specifications Packet. Engineer's estimate is \$325,000.

Work performed under this contract shall be based on a lump sum bid. Quantities, if shown in the construction plans, are estimated for bidding purposes only and shall be verified by the contractor.

Pay special attention to all notes shown in the construction plans.

Contractor shall video the project limits prior to beginning construction. The video shall be in DVD format and provided to Lake County before construction begins. Detail should be given to all existing fence lines, driveways, hedge lines, etc., to document existing conditions prior to construction.

Bid to sod all disturbed areas matching all existing grass types. Contractor shall be responsible for watering all sod until there is established growth.

All utilities shown in the construction plans to be relocated shall be the responsibility of the utility provider to relocate. The contractor shall be responsible for coordination of all utility adjustments and relocation.

Contractor shall provide two (2) red-lined, complete copies of plans as as-built drawings for the project.

Sidewalks shall be built with a maximum 2% cross slope. The construction plans state that ¼" per foot will be allowed. However, the contractor must pay special attention when pouring the sidewalk to ensure that the final cross slope does not exceed 2%.

#### **Questions Discussed at the Pre-Bid Meeting:**

**Question:** At top of Sheet 5 of the construction plans it states construct a five foot wide concrete sidewalk with detectable warnings and the line is hard to follow. Please clarify.

**Answer:** It is Lake County's intent to install a crosswalk at this intersection (see sheets S-4 and T-4 for clearer details). Therefore, contractor should bid to construct a five foot sidewalk that would extend from existing sidewalk and tie into edge of pavement at the proposed crosswalk.

**Question:** Does Lake County want to keep all the trees and have the sidewalk meander through the trees?

**Answer:** It is Lake County's intent to remove only those trees which are shown as being removed in the construction plans. The majority of the oak trees will remain and the sidewalk will meander around the trees.



---

Terry Scott, Construction Inspector II