

ADDENDUM #1

CR 561 Restriping from US 27 to CR 48
FPN #429608-1-58; FAN #5805-001-S
Project No. 2014-02
Bid No. 14-0008

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-4 of the bid proposal.** Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

A non-mandatory pre-bid meeting for the referenced project was held at 9:30 a.m. on November 7, 2013, in the Department of Public Works' conference room. The following were in attendance:

Name	Company	Phone Number	Email Address
Mike Olson	Traffic Solutions	(407) 301-8807	Molson@trafficsolutionsfl.com
Denis Dietz	Lake County Public Works	(352) 742-1766	ddietz@lakecountyfl.gov
Paul Erickson	Lake County Public Works	(352) 483-9021	perickson@lakecountyfl.gov
Terry Scott	Lake County Public Works	(352) 483-9024	jscott@lakecountyfl.gov
Gary Carbino	Lake County Public Works	(352) 483-9027	gscarbino@lakecountyfl.gov
Heath McArdle	Lake County Public Works	(352) 483-9023	hmcardle@lakecountyfl.gov
Deb Marchese	Lake County Public Works	(353) 483-9007	dmarchese@lakecountyfl.gov

This project is located along CR 561 from CR 48 in Astatula to US Highway 27 in Minneola and will consist of restriping CR 561 with raised audible vibratory markings. Other work associated with this project shall include the following: restriping turn lanes, arrows, and stop bars with thermoplastic striping, and other miscellaneous incidental construction. The engineer's estimate is \$305,515.

This project is a LAP project and all Federal and State standards must be met.

Work performed under this contract shall be based on a lump sum bid. Quantities, if shown in the construction plans, are estimated for bidding purposes only and shall be verified by the contractor.

Pay special attention to all notes shown in the construction plans.

Contractor shall video the project limits prior to beginning construction. The video shall be in DVD format and provided to Lake County before construction begins.

Bid to sod all disturbed areas matching all existing grass types. Contractor shall be responsible for watering all sod until there is established growth.

Changes to Bid Document and/or Construction Plans:

Contractor shall add a line item for **Removal of Existing Striping** to the tabulation sheet and include the cost in their bid estimate. Removal of the existing striping may be done by either grinding or hydroblasting.

On Sheet 27 of the construction plans, the white skips shown in the center of the roadway at Station 381+00 shall be **yellow** instead of white.

Questions Asked at the Pre-Bid Meeting

Q: Are there restrictions on the hours worked?

A: Contractor shall bid to work between the hours of 7:00 a.m. and 5:00 p.m., Monday through Friday. Any deviation in this work schedule will require prior Lake County approval.



Terry Scott, Construction Inspection Supervisor