

ADDENDUM #1

Kurt Street at Ardice Avenue/Mt. Homer Road Intersection Improvements
Project No. 2014-03, Bid No. 14-0010

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-4 of the bid proposal.** Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

A non-mandatory pre-bid meeting for the referenced project was held at 9:00 a.m. on December 5, 2013, in the Department of Public Works' conference room. The following were in attendance:

Name	Company	Phone Number	Email Address
Johnny Morris	Estep Construction	(407) 325-5998	jeff@estepconstruction.com
Lito Detorres	Art Walker/PDS	(352) 589-7000	Lito713@comcast.net
Ross Pluta	Lake County Public Works	(352) 483-9041	rpluta@lakecountyfl.gov
Terry Scott	Lake County Public Works	(352) 483-9023	jscott@lakecountyfl.gov
Gary Carbino	Lake County Public Works	(352) 483-9027	gscarbino@lakecountyfl.gov
Seth Lynch	Lake County Public Works	(352) 483-9052	slynch@lakecountyfl.gov
Heath McArdle	Lake County Public Works	(352) 483-9023	hmcardle@lakecountyfl.gov
Deb Marchese	Lake County Public Works	(353) 483-9007	dmarchese@lakecountyfl.gov

This project is located in Eustis and shall consist of sidewalk and drainage improvements at the intersection of Kurt Street, Ardice Avenue, and Mt. Homer Road, reconstructing the intersection and providing stormwater improvements. Other work associated with this project shall include the following: 1" milling, asphalt paving, Type F curb, valley curb, storm structure installation, sidewalk replacement, traffic loop replacement, thermoplastic striping, sodding, and other miscellaneous incidental construction. Engineer's estimate is \$150,000.

Work performed under this contract shall be based on a lump sum bid. Quantities, if shown in the construction plans, are estimated for bidding purposes only and shall be verified by the contractor.

Pay special attention to all notes shown in the construction plans. Sheet 4 of the construction plans has a special requirement for sidewalk and detectable dome mats.

Contractor shall video the project limits prior to beginning construction. The video shall be in DVD format and provided to Lake County before construction begins. Detail

should be given to all existing fence lines, driveways, hedge lines, etc., to document existing conditions prior to construction.

Bid to sod all disturbed areas matching all existing grass types. Contractor shall be responsible for watering all sod until there is established growth.

All utilities shown in the construction plans to be relocated shall be the responsibility of the utility provider to relocate. The contractor shall be responsible for coordination of all utility adjustments and relocation.

Contractor shall provide two (2) red-lined, complete copies of plans as as-built drawings for the project.

Contractor shall submit a lump sum bid, utilizing one of the blank lines in the bid tabulation sheet, for the following additional thermoplastic striping not shown on the construction plans:

1. On Kurt Street north of the intersection, 510 linear feet of gore area with 18 inch diagonals at 30 ft. intervals, 70 linear feet of double yellow striping.
2. On Mt. Homer Road west of the intersection, 405 linear feet of gore area with 18 inch diagonals at 30 ft. intervals.
3. On Ardice Avenue east of the intersection, 59 linear feet of double yellow striping, 1 additional turn arrow.
4. On Kurt Street south of the intersection, 452 linear feet of gore area with 18 inch diagonals at 30 ft. intervals, 10 linear feet of double yellow striping.

Contractor shall bid to remove two additional panels of sidewalk located at the northwest corner of the project (see attached photo). The Contractor shall bid to replace the sidewalk panels with sod.

 12-6-13
Gary Carbino, Construction Inspector I

Kurt Street at Ardice Avenue/Mt. Homer Road Intersection Improvements
Project No. 2014-03, Bid No. 14-0010

