

ADDENDUM #1

CR 445 Widening and Resurfacing (SR 19 to Hibiscus Road)
Project No. 2014-05
Bid No. 14-0012

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-4 of the bid proposal.** Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

A non-mandatory pre-bid meeting for the referenced project was held at 9:00 a.m. on February 27, 2014, in the Department of Public Works' conference room. The following were in attendance:

| Name | Company | Phone Number | Email Address |
|----------------|--------------------------|---------------------|--|
| Jeff Estep | Estep Construction | (407) 325-5998 | jeff@estepconstruction.com |
| Kathryn Barnes | D.A.B. Constructors | (352) 447-5488 | kathrynb@dabcon.com |
| Denis Dietz | Lake County Public Works | (352) 742-1766 | ddietz@lakecountyfl.gov |
| Terry Scott | Lake County Public Works | (352) 483-9024 | jscott@lakecountyfl.gov |
| Heath McArdle | Lake County Public Works | (352) 483-9023 | hmcardle@lakecountyfl.gov |
| Deb Marchese | Lake County Public Works | (353) 483-9007 | dmarchese@lakecountyfl.gov |

This project is located in North Lake County along CR 445. It shall consist of constructing paved shoulders. Other work associated with this project shall include the following: asphalt milling, thermoplastic striping, swale work, driveway construction, roadway signage, sodding, and other miscellaneous incidental construction. The engineer's estimate is \$438,200.00.

As part of this project, Contractor shall bid to place new striping on CR 445 from East Deer Road to Bridge #114047, approximately 26,750 feet. The striping shall meet or exceed FDOT standard for "Painted Pavement Markings", Section 710 of the FDOT Standard Specifications for Road and Bridge Construction 2014. Thermoplastic striping is not required, and the existing striping pattern must be followed. Removal of the old striping is not required, the intent is to install new painted striping over the existing striping. Bidders shall be required to provide an alternate bid for this work. Engineer's estimate for this alternate bid is \$46,800.00. Please note this is a change to the requirements shown in the Bid Document and the FDOT Section Number referenced on the construction plans has been changed.

Work performed under this contract shall be based on a lump sum bid. Quantities, if shown in the construction plans, are estimated for bidding purposes only and shall be verified by the contractor.

Pay special attention to all notes shown in the construction plans. On sheet 3 under Public Notification, we will be requiring a minimum of 14 days for resident notification and a variable message board shall be put up one week prior to construction.

Contractor shall video the project limits prior to beginning construction. The video shall be in DVD format and provided to Lake County before construction begins. Detail should be given to all existing fence lines, driveways, hedge lines, etc., to document existing conditions prior to construction.

Bid to sod all disturbed areas matching all existing grass types. Contractor shall be responsible for watering all sod until there is established growth.

Contractor shall coordinate all utility relocation with the responsible utility provider. It is the responsibility of each utility owner to relocate their facilities as needed to avoid conflicts.

Contractor shall provide two (2) red-lined, complete copies of plans as as-built drawings for the project.

All millings shall remain the property of Lake County. The Contractor shall bid to haul the millings to the Umatilla Maintenance Barn located at 19720 East Fifth Street, Umatilla, FL. Millings shall not be stockpiled on the project site.

This project requires the use of the safety edge. The County wants this tapered edge placed on the six (6) inches of additional base material at the edge of pavement.

Questions asked at the Pre-Bid Meeting

Q1: Does the County want the dirt that is removed from the ditches?

A1: No, Lake County does not want the dirt removed from the ditches. It is the contractor's responsibility to dispose of the excess material.

Q2: Is the Contractor to use thermoplastic striping where the widening and resurfacing is done, but not in the section from East Deer Road to Bridge #114047?

A2: Contractor shall bid to place thermoplastic striping from SR 19 to Hibiscus Road. Contractor shall bid to place new striping on CR 445 from East Deer Road to Bridge #114047, approximately 26,750 feet. The striping shall meet or exceed FDOT standard for "Painted Pavement Markings", Section 710 of the FDOT Standard Specifications for Road and Bridge Construction 2014.



Heath McArdle
Construction Inspection II