

ADDENDUM #1

CR 473 / Westmont Road Turn Lane
Project No. 2014-06
Bid No. 14-0013

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-4 of the bid proposal.** Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

A non-mandatory pre-bid meeting for the referenced project was held at 9:00 a.m. on January 30, 2014, in the Department of Public Works' conference room. The following were in attendance:

Name	Company	Phone Number	Email Address
Mike Davis	Central Testing Lab.	352-302-0657	Mdavis@ctfl.com
Denis Dietz	Lake County Public Works	(352) 742-1766	ddietz@lakecountyfl.gov
Terry Scott	Lake County Public Works	(352) 483-9024	jscott@lakecountyfl.gov
Michelle Bilbrey	Lake County Public Works	(352) 483-9020	mbilbrey@lakecountyfl.gov
Deb Marchese	Lake County Public Works	(353) 483-9007	dmarchese@lakecountyfl.gov

This project is located in Leesburg along CR 473 and shall consist of constructing a northbound center turn lane onto Westmont Road. Other work associated with this project shall include the following: asphalt milling, SP 9.5 asphaltic concrete, SP 12.5 asphaltic concrete, thermoplastic striping, storm pipe and structure installation, driveway construction, roadway signage, sodding, and other miscellaneous incidental construction. Engineer's estimate is \$164,938.

This project is a LAP project and all FDOT standards must be met.

Work performed under this contract shall be based on a lump sum bid. Quantities, if shown in the construction plans, are estimated for bidding purposes only and shall be verified by the contractor.

Pay special attention to all notes shown in the construction plans.

Contractor shall video the project limits prior to beginning construction. The video shall be in DVD format and provided to Lake County before construction begins. Detail should be given to all existing fence lines, driveways, hedge lines, etc., to document existing conditions prior to construction.

Bid to sod all disturbed areas matching all existing grass types. Contractor shall be responsible for watering all sod until there is established growth.

All utilities shown in the construction plans to be relocated shall be the responsibility of the utility provider to relocate. Utility coordination shall be the contractor's responsibility.

Contractor shall provide two (2) red-lined, complete copies of plans as as-built drawings for the project.

No concrete shall be installed around sign posts.



Terry Scott
Construction Inspection Supervisor