

Delivery and Installation of Pavers
Ellis Acres Reserve- 35302 County Road # 42 Paisley, FL 32767

SCOPE OF WORK: Provide all labor, materials, equipment, fuel and other incidental costs and supervision necessary for the removal of existing carpet in lanai area and install new pavers. All work and equipment shall be in strict compliance with the latest codes, standards and practices.

Flooring Specifications:

Pavers: Brick Pavers, **or approved equal**, laid in a hopscotch pattern

Total estimated 415 SF

Room: Lanai (outside)

Seal pavers twice, applying evenly and following manufacturers instructions.

Estimated 400 SF removal of glued down carpet on lanai

There will be no flooring changes made to the bathrooms at this time.