North Lake Community Park- 40730 Roger Giles Rd. Umatilla, FL 32784 East Lake Community Park- 24809 Wallick Rd. Sorrento, FL 32776 Minneola Athletic Complex-1300 Fosgate Rd. Minneola, FL 34715 P.E.A.R Park-26701 US Highway 27, Leesburg, FL 34748 Paisley Community Park- 24956 CR# 42 Paisley, FL 32767 Pine Forest Park- 32520 SR# 44 Deland, FL 32720 Astor Lions Park- 54835 Alco Rd. Astor, FL 32102

1.01 SCOPE OF WORK: Provide all labor, materials, equipment, fuel and other incidental costs and supervision necessary for the installation of 3000 linear feet of 6' Black windscreen & 4000 Linear feet of 5' Black Windscreen. Windscreen to match existing at County Parks. All work and equipment shall be in strict compliance with the latest codes, standards and practices.

### Misc. Items to be noted:

- Field verification by Contractor is recommended
- Windscreen is to be Black and 6FT high with vents on the top and bottom every 5FT on center
- Vinyl coated Polyester-Fabric 50% vinyl,50% polyester, open (VCP)- 9X12 weave
- Windbreak: open- 80%
- Weight per square yard: open- 7oz
- Tensil strength: open 230 X 200
- Screen to be installed with break away ties on top and sides and rope on the bottom
- Windscreen to be installed on all gates
- Screen must have a least a 3 year warranty
- Vendor / Installer must tailor windscreen to each tennis & pickle ball fence ( i.e. keeping in mind fence section breaks/ panels/ openings and copy the existing windscreen design
- All work must be completed within 10 days from the issuance of the purchase order or notice to proceed.
- Work to be performed only as needed.

#### 1.02 SUBMITTALS:

- A. Submit product data/specification and shop drawings to Park and Trails Division for review and approval of all items of work.
- 1.03 FIELD CONDITIONS: Verify and coordinate all work to field locations and dimensions.

# PART III - EXECUTION

# 3.01 WORKMANSHIP:

- A. All furnishings described herein shall be installed by qualified tradesman. All installation work and materials to be per manufacturer's specifications, or as directed by the Owner's Representative.
- B. Install as per manufacturer's specifications.

### 3.4 CLEANING

A. Perform cleaning during installation of the work and upon completion of the work. Remove from site all excess materials, soil, debris, and equipment.



