

Delivery and Installation of Tile and/or Solid Vinyl
Ellis Acres Reserve- 35302 County Road # 42 Paisley, FL 32767

SCOPE OF WORK: Provide all labor, materials, equipment, fuel and other incidental costs and supervision necessary for the removal and proper disposal of the existing carpet, pad, tack & vinyl flooring throughout the entire residence (bathrooms not included) and install new tile and solid vinyl flooring. All work and equipment shall be in strict compliance with the latest codes, standards and practices.

Flooring Specifications:

Tile: Happy Fusion Musk 12" x 24" **or approved equal**, laid in a brick pattern.

Total estimated 1225 SF

Rooms: Hallways, front reception area, living room and kitchen.

Estimated 1130 SF removal of existing carpet, pad and tack in hallways, front reception area, living room and kitchen.

Grout color to be approved by Parks and Trails Division.

Solid Vinyl: Shaw North Hampton Click & Lock Floating Belmont Hickory 00250, **or approved equal.**

Total estimated 1345 SF

Rooms: Bedrooms (offices) and closets

Estimated 1230 SF removal of existing vinyl and carpet, pad and tack in bedrooms (offices) and closets

10 reducers from tile to vinyl.

400 LF of primed white 1/4" round for vinyl areas.

4 baby thresholds.

There will be no flooring changes made to the bathrooms at this time.