

## **Paver Replacement Bid For:**

Lake County Courthouse  
550 W. Main St.  
Tavares, FL 32778

### **GENERAL**

1. Perform all work in accordance with applicable codes, local ordinances, and requirements of Lake County, FL.
2. The Contractor shall provide all required materials, labor, equipment, plans, engineering, zoning approval, permits and inspections to provide a 100% completed project.

### **SCOPE OF WORK**

1. The Contractor shall remove the existing pavers and concrete as specified.
2. After the removal of the existing pavers and concrete all earth shall be compacted to 95% compaction with a plate compactor. No density test shall be required provided the virgin soil is moist and compacted to the satisfaction of the Lake County Project Manager.
3. Upon completion of forming for each upcoming pour, the Contractor will contact the Lake County Project Manager to perform a site visit to review the site for the upcoming pour. The Contractor will provide the Lake County Project Manager with at least 24 hour notice. No concrete pours will be made without approval from the Lake County Project Manager.
4. All concrete work shall be performed in accordance with accepted industry standards and codes for cast-in-place concrete including, but not limited to, temperature recommendations, reinforcing, measuring, transporting, and placing of concrete.
5. Due to limited access concrete shall be mixed and poured on site.
6. All concrete shall have a minimum compressive strength of 4000 psi at 28 days.
7. Concrete thickness shall match existing with a minimum of 4".
8. Concrete edges shall be tooled to match existing.
9. 6"x 6"x10ga. welded wire mesh shall be installed.
10. Expansion and contraction relief to be provided by the use of bituminous material on the edges and saw cuts in the field.
11. Expansion and contraction relief shall be spaced no more than 10' apart and shall match existing.
12. Saw cuts shall be made within 4-12 hours after concrete finishing.
13. Saw cuts shall have a depth that is equal to 25% of slab thickness.
14. Concrete shall have a light non-slip broom textured finish to match existing.
15. All work must be completed within 30 calendars after the P.O. has been issued.
16. All pavers and metal tree bed grates shall be palletized and delivered to 32400 CR 473 Leesburg, FL 34788.