

South Lake Trail Aluminum Safety Railing & Bike Lean Replacement

- 1.01 SCOPE OF WORK: Provide all labor, materials, equipment, fuel and other incidental costs and supervision necessary to furnish, deliver and install new 40 FT. of Aluminum Safety Rail & Three (3) New Bike Leans on the South Lake Trail located on Old Hwy 50 North West on County Road 455 in Clermont, FL 34715. All work and equipment shall be in strict compliance with the latest codes, standards and practices.

Misc. Items to be noted:

- Field verification by Contractor recommended.
 - Work to be completed within 15 days after issuance of Purchase Order.
 - **See attached photo for details.**
 - **Replace all damaged Safety Railing (approximately 40 FT. Long X 54 ½ INCH High, 3 rail Aluminum Rail)**
 - **Replace 1 Custom Bike Lean (Blacksill Lake Rd.& Old Hwy #50) 18 FT. Long X 42 INCH High) and 2 Standard Bike Rails (9 FT. Long X 54 INCH High, 2 rail Aluminum Rail)**
 - **Contractor to verify condition of safety rail & bike lean dimensions as necessary included in this bid.**
 - **Work area must be cautioned off while repairs are made.**
- 1.02 FIELD MEETING: Coordinate all work with Chris Macdonald (352) 460-2902 Lake County Parks & Trails. 72 hour prior notice required.
- 1.03 SUBMITTALS:
- A. Submit product samples to Parks & Trails Division for review and approval prior to Contractor delivering materials to site.
- 1.04 ACCEPTANCE:
- A. The County's Parks & Trails Division will review each installation to determine compliance prior to final acceptance of the work.
- PART III – EXECUTION
- 3.01 WORKMANSHIP:
- A. All repair work described herein shall be installed by qualified tradesman. All installation work and materials to be per manufacturer's specifications, or as directed by the Owner's Representative.
- 3.02 CLEANING:
- A. Contractor to perform cleaning during daily installation of the work & upon completion of the work. Remove from site all excess materials, debris & equipment.



