

## **Poured in Place Rubber Surface Repairs at Lake Idamere Park Playground**

- 1.01 SCOPE OF WORK: Provide all labor, materials, equipment, fuel and other incidental costs and supervision necessary to remove the existing broken/ damaged rubber surface material and to furnish and install 2000 Square FT. of new poured in place Rubber Surface throughout the various areas of the playground at Lake Idamere Park-12335 CR 448 Tavares, FL 32778. All work and equipment shall be in strict compliance with the latest codes, standards and practices.

### **Misc. Items to be noted:**

- Field verification by Contractor recommended.
  - Work to be completed within 15 days after issuance of Purchase Order.
  - **Must submit color photo/ sample of product for approval**
  - **See attached photo for details.**
  - **Rubber surface colors green, blue and maroon.**
  - **Work area must be cautioned off at all times.**
  - **All repairs are to be made in squares, circles, or other shapes as approved by the Parks & Trails Division.**
- 1.02 FIELD MEETING: Coordinate all work with Chris Macdonald (352) 460-2902 Lake County Parks & Trails. 72 hour prior notice required.
- 1.03 SUBMITTALS:
- A. Submit product samples to Parks & Trails Division for review and approval prior to Contractor delivering materials to site.
- 1.04 ACCEPTANCE:
- A. The County will review each installation to determine compliance prior to final acceptance of the work.

## **PART III – EXECUTION**

- 3.01 WORKMANSHIP:
- A. All materials are subject to the approval of the County.
- B. All repair work described herein shall be installed by qualified tradesman. All installation work and materials to be per manufacturer's specifications, or as directed by the Owner's Representative.
- 3.02 CLEANING:
- A. Contractor to perform cleaning during daily installation of the work & upon completion of the work. Remove from site all excess materials, debris & equipment.















