ADA Truncated Domes for Various County Parks

1.01 SCOPE OF WORK: Provide all labor, materials, equipment, fuel and other incidental costs and supervision necessary to furnish and install 50 new ADA compliant Truncated Domes at Various County Parks. All work and equipment shall be in strict compliance with the latest codes, standards and practices.

Misc. Items to be noted:

- ADA compliant truncated domes per FDOT # 304.
- Dimensions- 60 INCH LONG X 24 INCH WIDE 13/32 INCH THICK.
- Grainger product or approved equal.
- Yellow in color.
- **Must submit photo/ sample of product for approval**
- **See attached photo for details.**
- **Truncated domes cut to size as required,**

1.02 FIELD MEETING: Coordinate all work with Shane Strew 352-516-4916 Lake County Parks & Trails. 72 hour prior notice required.

1.03 PRODUCT HANDLING:

A. Deliver products to site in manufacturer's containers or packaging.

B. Store in secure area.

C. Return all damaged products to manufacturer.

PART III – EXECUTION

3.01 WORKMANSHIP:

A. All materials are subject to the approval of the County.

B. All products shall be inspected by the County for damage and chipped or marred finish. Contractor shall replace any damaged or rejected products at no conditional cost to the owner. The owner's representative may at his option authorize acceptance of chipped or scratched painted surfaces repaired by contractor at his own risk