

OVERHEAD PROTECTIVE NETTING

LOCATION: Minneola Athletic Complex, 1300 Fosgate Road, Minneola FL 34715

Scope of Work:

Furnish and install Overhead Protective Netting.

The contractor shall furnish all labor, equipment, materials, fuel and any other incidental costs, and supervision necessary for the installation and completion of the Overhead Protective Netting.

- Netting 1 ¾"-#36 three-strand twisted twine-knotted netting-1 ¾" mesh-latex & U.V. treated black for a 4 field ballpark overhead protection configuration.
- Netting to cover from between four fields.
- Nets will be hung from existing building to existing chain link fence on cables and around the building. Fasteners to be used on the building structure.
- All connections to the existing building must be made above the windows and closer to the roof framing.

Price should include: All netting, cable, hardware machinery and labor to install the above described barrier netting fence.

VENDORS MUST VISIT PARK SITE FOR INSPECTION AND MEASUREMENTS OF SQUARE FOOTAGE. MEASUREMENTS WILL NOT BE PROVIDED BY THE COUNTY.

See attached photos for additional information.