

Sand Live Oak Trees at Various County Park & Public Lands Properties

- 1.01 SCOPE OF WORK: Provide all labor, materials, equipment, fuel and other incidental costs and supervision necessary to furnish, delivery & installation of 150- 15 gallon (4FT.- 6FT.) sand live oak trees at Various County Parks & public Lands Properties. All work and equipment shall be in strict compliance with the latest codes, standards and practices.

Misc. Items to be noted

1. Watering: The County requests that the Contractor water the trees that they have installed for ten (10) consecutive days. Contractor must provide water. Each tree must receive at least 30 gallons of water per watering. Price is deemed included in the per tree price.

Note: All materials are subject to approval of the County.

- **Coordinate all work with Dwayne Henry 352-516-2655 Lake County Parks & Trails. (48 hours notice required.)**
- **Vendor must submit photos of sand live oak tree samples for approval.**
- **Spacing of tree will be determined by Lake County staff (typical 15 FT. from center spacing).**
- **Irrigation is not available. Contractor must provide water.**
- **Trees deemed unhealthy will be rejected by the Parks staff before planting.**
- **Three (3) deliveries of 50 trees each delivery, in three (3) separate weeks.**

- 1.02 SITE CONDITIONS: Verify and coordinate all work installations to locations on attached map.