

## **Retention Pond: Erosion repairs**

East Lake Community Park: 24809 Wallick Rd. Sorrento, FL 32776

- 1.01 **SCOPE OF WORK:** Provide all labor, materials, equipment, fuel and other incidental costs and supervision necessary to furnish clean fill material as necessary including cutting, filling, grading, rolling and compaction then sodding all the disturbed slope areas, the entire bottom of the retention pond and from the slope to the orange construction fence, all newly sodded areas need to be rolled. All work and equipment shall be in strict compliance with the latest codes, standards and practices.

### **Misc. Items to be noted:**

- Site verification by Contractor is mandatory
- Bahia sod
- See attached photos & map for details

- 1.02 **FIELD CONDITIONS:** Verify and coordinate all work to field locations and dimensions. Contractor is responsible for the installation of temporary construction fencing and signage to safely enclose the work area.

### **1.03 PRODUCT HANDLING:**

- A. Deliver products to site in manufacturer's containers or packaging.
- B. Store in secure and weather protected area.
- C. Return all damaged products to manufacturer.

## **PART II – PRODUCTS**

- 2.01 **MATERIALS:** Provide products as called for on the drawing and specified herein. See furnishing schedule and descriptions on drawings for specific products and Manufacturer's specs.

## **PART III – EXECUTION**

### **3.01 WORKMANSHIP:**

- A. All furnishings described herein shall be installed by qualified tradesman. All installation work and materials to be per manufacturer's specifications, or as directed by the Owner's Representative.
- B. All work and materials are subject to the approval of the County.
- C. All products shall be inspected by the County for damage and chipped or marred finish. Contractor shall replace any damaged or rejected products at no conditional cost to the owner. The owner's representative may at his option authorize acceptance of chipped or scratched painted surfaces repaired by contractor at his own risk.

### 3.1 INSTALLATION

- A. Install furnishing in locations as indicated on the plans and details. Assure that all furnishings are installed plumb and level and in accordance with the plans and details.
- B. Install as per manufacturer's specifications

### 3.2 ACCEPTANCE

- A. The County will review each installation to determine compliance with plans and specifications prior to final acceptance of the work.
- B. Any work not installed in accordance with the plans and specifications and rejected by the County shall be removed and replaced at the Contractor's expense.

### 3.3 GUARANTEES

- A. The contractor shall furnish warranties in writing certifying that the quality and workmanship of all materials and installation furnished is in accordance with these specifications and in accordance with the original manufacturers' warranties. The contractor shall warrant the installation workmanship for a period of 90 days from the date of final acceptance of the job, or any accepted portion of the job.

### 3.4 CLEANING

- A. Perform cleaning during installation of the work and upon completion of the work. Remove from site all excess materials, soil, debris, and equipment.