

Pre-Bid – Addendum #4

#1346 Hooks Street Extension Phase IV-B
Project No. 2011-06
Bid No. 11-0025
FM # 419665-2-58-01

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-5 of the bid proposal.** Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

Please clarify the following items:

- Q1. Provide a detail for the wall drain shown on sheet 8 of 18.
Provide stations for the start and end of the toe drain shown on the wall drawings.
- A1. The plan limits of the drain at the toe of the wall are shown on drawing sheet 16 of 18, extending from approximate mainline station 46+00 to the end of the wall on the access road going north. The drainpipe and geotextile wrap should comply with FDOT Standard Detail Index No 286.
- Q2. Bid Item 6 Over excavation of pond, where is this work shown on the drawings?
A2. Over excavation of the retention pond may be required to meet the required pond bottom elevation shown in the construction plans. If over excavation is required the contractor include in their bid the cost to perform this work.
- Q3. Detail for typical slope soil stabilization, please clarify where/when is this required.
A3. Slope soil stabilization is required where soil slope is 2:1 or steeper; this is mostly required in the northern side slopes of the proposed road. Please refer to the cross-sections for locations.

Approved by:



Lori Conway, Funding & Production Director



Date

:smcd