

**Addendum #2**

Lake Eustis Drive/Lakeshore Drive Stormwater Improvement  
Project No. 2011-05  
Bid No. 11-0027

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-4 of the bid proposal.** Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

**Questions & Answers submitted via email on July 12, 2011:**

- Q.** On sheet 3 – For the type E & F curbs it shows 1.5" but then says to use Group 9, which is 6". Please clarify if this is to be 1.5" or the 6" per Group 9.
- A.** Bid to construct the curb pad using optional base group 9 per FDOT Index No. 514. Lake County will allow the use of limerock 6" in depth, 98% compaction as a substitution for the optional base group 9.

**Q.** Is the bid tab available in Excel format?

- A.** Yes, the bid tabulation sheet is located on the FTP site at the following link:

[ftp://ftp.co.lake.fl.us/Public\\_Works/Funding\\_Production/Lake%20Eustis%20Lakeshore%20Drive%20Stormwater%20Improvements/](ftp://ftp.co.lake.fl.us/Public_Works/Funding_Production/Lake%20Eustis%20Lakeshore%20Drive%20Stormwater%20Improvements/)

Additional spaces have been provided at the bottom of the "Bid Form - Tabulation of Estimated Quantities" sheet. If needed, the bidders can write in any additional items needed that are not listed on the "Bid Form - Tabulation of Estimated Quantities" sheet. No other modification shall be made to this form.

**Q.** Are the cad files available for material & earthwork takeoff purposes?

- A.** Yes, the CAD file is located on the FTP site at the following link:

[ftp://ftp.co.lake.fl.us/Public\\_Works/Funding\\_Production/Lake%20Eustis%20Lakeshore%20Drive%20Stormwater%20Improvements/](ftp://ftp.co.lake.fl.us/Public_Works/Funding_Production/Lake%20Eustis%20Lakeshore%20Drive%20Stormwater%20Improvements/)


**Q.** Are we allowed temporary road closures for crossing installation on this project?

- A.** Lake County will not allow the complete closure of Lake Eustis Drive/Lakeshore Drive. The contractor shall bid to construct the project keeping one lane of traffic open at all times. All lanes of traffic must be open at the end of each work day.

**PLAN REVISIONS**

As part of the bid package for the Lake Eustis Drive/Lakeshore Drive Stormwater Improvement Project bidders were provided with replacement sheets numbered 7, 19, 41, 42, 43, 44, 45, 46, 47, 48, and 49. These plan sheets were prepared by the Lake County Public Works Department and are dated February, 2011. On plan sheets 41 thru 49 the existing cross slopes are not accurately depicted. However, the contractor shall bid to construct the swales from the edge of pavement as shown in these revised cross sections (1:5 slopes). Also, the contractor shall bid to mill and resurface the roadway in this area using the typical section shown on sheet 3 of the DRMP construction plans. The contractor shall place the type E and type F curb to align with the final pavement grade.

Approved by:

  
\_\_\_\_\_  
Jeff Johnson, Construction Inspection Manager

7/14/11  
\_\_\_\_\_  
Date

:smcd