Pre-Bid – Addendum #1
CR-561 Sidewalk
Project No. 2011-10
Bid No. 12-0018

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-3 of the bid proposal**. Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

A non-mandatory pre-bid meeting for the referenced project was held at 9:30 a.m. on December 15, 2011 in the Department of Public Works' conference room. The following were in attendance:

Name	Company	Phone Number	Email Address
Kathryn Barnes	D.A.B. Constructors, Inc	(352) 447-5488	kathrynb@dabcon.com
David Berger	Lake County Public Works	(352) 394-2559	dberger@lakecountyfl.gov
J. J. Bonnisuto	Flamingo Concrete	(352) 552-7874	jjflamingo@gmail.com
Denis Dietz	Lake County Public Works	(352) 742-1766	ddietz@lakecountyfl.gov
Seth Lynch	Lake County Public Works	(352) 483-9052	slynch@lakecountyfl.gov
Sherry McDermott	Lake County Public Works	(352) 483-9020	smcdermott@lakecountyfl.gov
Ross Pluta	Lake County Public Works	(352) 483-9041	rpluta@lakecountyfl.gov
Ron Rudolph	Lake County Public Works	(352) 483-9021	rrudolph@lakecountyfl.gov
Terry Scott	Lake County Public Works	(352) 483-9023	jscott@lakecountyfl.gov
Reggie Tietjen	Wagner 3	(352) 787-5540	
Jerome Wilson	Jerome's Masonry, Inc.	(352) 750-3555	jeromesmasonryinc@hotmail.com
Rafael Icaea	Stones Unlimited	(407) 508-4047	stonesunlimited@hotmail.com

This project is located south of Tavares along CR-561 and shall consist of constructing sidewalk approximately 2,245 linear feet. Other work associated with this project shall include the following: asphalt removal, limerock, type F curb, concrete flume, detectable warnings, thermoplastic striping, swale work, and other miscellaneous incidental construction.

- Pay special attention to all general notes on the construction plans.
- Contractor to install VMS Boards 7 days prior to construction.
- Cost of all required laboratory testing shall be borne by the Contractor. Testing shall be in accordance with the Standard Specifications.
- On sheet C-6 there is a storm structure with a manhole lid located in the paved shoulders at pavement grade. The Construction plans say to "raise top flush with sidewalk". Include in your bid the cost to adjust this manhole top.

- Contractor shall provide two (2) red lined, complete copies of plans as as-built drawings for the project.

- Contractor shall video the project limits prior to beginning construction. The video shall be in DVD format and provided to Lake County **before** construction begins. Detail should be given to all existing fence lines, driveways, hedge lines, etc., to document existing conditions prior to construction.

- Bid to sod all disturbed areas matching all existing grass types. Contractor shall be responsible for watering all sod until there is established growth.

- Work performed under this contract shall be based on a lump sum bid. Quantities, if shown in the bid, are estimated for bidding purposes only and shall be verified by the contractor.

- The Engineers Estimate is $75,000.00.

- This is a FDOT funded project and all federal and state requirements are applicable to this project. This is not an ARRA project.

- The right-of-way will be staked by Friday, December 16, 2011.

- Any questions shall be submitted in writing by **December 20, 2011** to Sherry McDermott via email at smcdermott@lakecountyfl.gov and will be responded to through the issuance of an addendum. **Please be sure that all addendums are acknowledged by signing and dating the appropriate line on page W-3 of the bid proposal.** Addendums will be posted on Lake County's Procurement Services website. The website link for this project is provided below:
  http://www.lakecountyfl.gov/departments/county_manager/procurement_services/bid_details.aspx?bid_number=12-0018

Questions and Answers:

Q. How many days to complete the project?

A. The Contractor shall submit the number of calendar days to complete the project.

Approved by:

Terry Scott, Construction Inspection II — Date 12-16-11

:smcd