ADDENDUM #1

CR 445 – Hibiscus Road to East Deer Road – Widening and Resurfacing
Project No. 2012-06
Bid No. 13-0001

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-4 of the bid proposal**. Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

A non-mandatory pre-bid meeting for the referenced project was held at 9:00 a.m. on September 20, 2012, in the Department of Public Works' conference room. The following were in attendance:

Name	Company	Phone Number	Email Address
Jennings Griffin	SSMC	(352) 343-4880	jgriffin@SSMC.us
Kathryn Barnes	D.A.B. Constructors	(352) 447-5488	kathrynb@dabcon.com
Victor Monroy/ Christina Tabor	CFE Corporation	(407) 947-5699	Ctabor75@aol.com
Holly Strout	WBE Environmental d/b/a/ Florida Silt	(386) 804-8696	hstrout@flsilt.com
Lito Detorres	PDS, Inc.	(352) 589-7000	professionaldirt@earthlink.net
Jeff Johnson	Lake County Public Works	(352) 483-9024	jjohnson@lakecountyfl.gov
Ron Rudolph	Lake County Public Works	(352) 483-9021	rrudolph@lakecountyfl.gov
Pat Magno	Lake County Public Works	(352) 483-9053	pmagno@lakecountyfl.gov
Deb Marchese	Lake County Public Works	(353) 483-9007	dmarchese@lakecountyfl.gov

This project is located in North Lake County along CR 445. It will consist of constructing radius improvements and paved shoulders. Other work associated with this project shall include the following: asphalt milling, thermoplastic striping, swale work, driveway construction, roadway signage, sodding, and other miscellaneous incidental construction. The engineer's estimate is $571,693.

Work performed under this contract shall be based on a lump sum bid. Quantities, if shown in the construction plans, are estimated for bidding purposes only and shall be verified by the contractor.

Pay special attention to all notes shown in the construction plans. On sheet 3 under Public Notification, we will be requiring a minimum of 14 days for resident notification and variable message board shall be put up one week prior to construction.

Page 4 of the Construction Plans states " Contractor shall de-silt all drains, pipes, and swales within the project boundaries at completion of construction."

Contractor shall video the project limits prior to beginning construction. The video shall be in DVD format and provided to Lake County before construction begins. Detail should be given to all existing fence lines, driveways, hedge lines, etc., to document existing conditions prior to construction.

Bid to sod all disturbed areas matching all existing grass types. Contractor shall be responsible for watering all sod until there is established growth.

All utilities shown in the construction plans to be relocated shall be the responsibility of the utility provider to relocate.

Contractor shall provide two (2) red-lined, complete copies of plans as as-built drawings for the project.

Lake County shall be responsible for the permitting and relocation of gopher tortoises within the project limits prior to construction.

Questions Discussed at the Pre-Bid Meeting:

Question: Are the typical sections going to be changed or are they going to remain as is?
Answer: There are no plans to change the typical sections.

Ron Rudolph, Construction Inspector II