

ADDENDUM #1

CR 565 (Villa City Road) Widening and Resurfacing
(Bible Camp Road to Simon Brown Road)
Project No. 2015-02, Bid No. 15-0011

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-4 of the bid proposal.** Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

A non-mandatory pre-bid meeting for the referenced project was held at 9:00 a.m. on March 12, 2015, in the Department of Public Works' conference room. The following were in attendance:

Name	Company	Phone Number	Email Address
Emily Boykin	Boykin Construction	(352) 394-5993	boykinconst@aol.com
Kathryn Barnes	D.A.B. Constructors	(352) 447-5488	kathrynb@dabcon.com
Tim Walker	Art Walker Construction	(352) 629-1466	office@artwalkerconstruction.com
Daniel Whalen	Andreyev Engineering	(305) 439-1137	dwhalen@andreyevengineering.com
Denis Dietz	Lake County Public Works	(352) 742-1766	ddietz@lakecountyfl.gov
Paul Erickson	Lake County Public Works	(352) 483-9021	perickson@lakecountyfl.gov
Terry Scott	Lake County Public Works	(352) 483-9024	jscott@lakecountyfl.gov
Alan Kirkland	Lake County Public Works	(352) 483-9043	akirkland@lakecountyfl.gov
Deb Marchese	Lake County Public Works	(353) 483-9007	dmarchese@lakecountyfl.gov

This project is located in Groveland and shall consist of constructing 3' paved shoulders along CR 565 / Villa City Road from Bible Camp Road to Simon Brown Road. Other work associated with this project shall include the following: 2" minimum SP 12.5 asphalt, Traffic Level C with modified polymer, asphalt milling, thermoplastic striping, storm structure installation, swale work, driveway construction, roadway signage, sodding, and other miscellaneous incidental construction. The engineer's estimate is \$1,531,196.00.

Work performed under this contract shall be based on a lump sum bid. Quantities, if shown in the construction plans, are estimated for bidding purposes only and shall be verified by the contractor.

Cost of all required laboratory testing shall be borne by the County with the exception of the cost of failing tests and subsequent re-tests which shall be borne by the Contractor. Testing shall be in accordance with the Standard Specifications.

Pay special attention to all notes shown in the construction plans.

Contractor shall note on Sheet 101 of the Construction Plans in the Section "Asphalt Safety Edge Detail" the 1" Type FC-9.5 Superpave asphalt overlay is not required as part of this project.

Contractor shall video the project limits prior to beginning construction. The video shall be in DVD format and provided to Lake County before construction begins. Detail should be given to all existing fence lines, driveways, hedge lines, etc., to document existing conditions prior to construction.

Bid to sod all disturbed areas matching all existing grass types. Contractor shall be responsible for watering all sod until there is established growth.

All utilities shown in the construction plans to be relocated shall be the responsibility of the utility provider to relocate. Contractor shall be responsible for coordinating the relocation of utilities.

Contractor shall provide two sets of redline as-builts upon completion of the project that show all structure locations, invert elevations, and pipe locations. The as-builts must be signed and sealed by a professional engineer or surveyor, licensed to do business in the State of Florida.

All millings shall remain the property of Lake County. The Contractor shall haul the millings to the SR 19 Clay Pit located at 10527 SR 19 (actually Allegiance Court), Groveland, FL. Millings shall not be stockpiled on the project site.

This project requires the use of the safety edge. The County wants this tapered edge placed on the six (6) inches of additional base material at the edge of pavement. Sheet 101 of the construction plans contains a note with the details of the safety edge and Contractor shall pay special attention to this note. Also note, this detail references 1" FC 9.5 Super Pave for the top lift. This 1" Type FC 9.5 Super Pave asphalt is not required for this project.

Questions Asked at the Pre-Bid Meeting

Q1: Is the geo-mat shown under the pipe on Sheet 23 of the construction plans the only place this geo-mat is required? Are there other pipes where the geo-mat shall be required?

A1: Contractor shall bid to install geo-mat under the structure shown on Sheet 23, with the details of the geo-mat shown on Sheet 102. This structure appears to be the only structure where geo-mat is required.

Q2: Are there CADD files available for this job?

A2: The CADD files are available at the following link:
ftp://ftp.lakecountyfl.gov/Public_Works/Engineering/CR%20565%20Villa%20City%20Road%20-%20Widening%20%26%20Resurfacing/



Paul Erickson, Construction Inspector I

3 16 2015
Date