ADDENDUM #2

CR 44C (Eudora Road) and Sylvan Shores Sidewalk Retrofit
Project No. 2015-04
Bid No. 15-0028

This addendum is being issued to make the following changes, corrections, clarifications and additions to the bidding document. The information in this addendum modifies and changes the original bidding documents and takes precedence over the original documents. **Receipt of this addendum shall be acknowledged by the bidder by signing and dating the appropriate line on page W-4 of the bid proposal**. Failure to acknowledge this addendum may preclude consideration of the bid proposal for award.

Questions Asked Via E-Mail

Q1: Please advise what the FDOT Approval Product Code for the "Root Barrier" on the referenced plans is.

A1: Contractor shall bid to install a Biobarrier Root Control Fabric. This is not an FDOT specified product, but it is a Lake County approved product.

Q2: FDOT Specs do not call for "commercial fiber" but plans specify "commercial fiber" – please confirm.

A2: Contractor shall bid to use residential fiber with a commercial grade mix and meet a minimum 3000 psi. Contractor shall bid to use an FDOT approved supplier for the concrete.

Q3: Is the 6" concrete being paid in the 4' or 5' sidewalk line item?

A3: Contractor shall bid to install 6" concrete as depicted on the construction plans.

Seth Lynch, Engineer II